

TOWN OF CASTLETON, VERMONT

CONTRACT DRAWINGS FOR CRYSTAL HEIGHTS SEWERLINE EXTENSION CONTRACT No.1

FEBUARY, 2024

AE
Aldrich + Elliott
WATER RESOURCE ENGINEERS
6 Market Place, Suite 2
Essex Jct., VT 05452
P. 802.879.7733
AEngineers.com

SELECTBOARD

JAMES LEAMY, CHAIRMAN
RICHARD COMBS, VICE CHAIRMAN
JOSEPH MARK, PARLIAMENTARIAN
ROBERT SPAULDING
MARY LEE HARRIS

TOWN MANAGER

MICHAEL A. JONES

PUBLIC WORKS DIRECTOR


DAVE FABRICUS

WASTEWATER TREATMENT FACILITY SUPERVISOR

RUSS HALLETT



PROJECT
LOCATION



INDEX OF DRAWINGS

<u>DRAWING No.</u>	<u>DRAWING TITLE</u>
T	TITLE SHEET AND INDEX OF DRAWINGS
1	GENERAL NOTES AND LEGEND
2	PROPOSED PLAN AND PROFILE STA. 0+00 TO 8+00
3	PROPOSED PLAN AND PROFILE STA. 8+00 TO 16+26
4	SEWER DETAILS I
5	SEWER DETAILS II
6	ROADWAY DETAILS
7	EROSION CONTROL DETAILS AND NOTES

LOCATION MAP
SCALE: 1"=500'

CHECKED	DESCRIPTION	DATE	No.

TOWN OF
CASTLETON,
VERMONT

CRYSTAL HEIGHTS
SEWERLINE
EXTENSION
CONTRACT No.1

TITLE SHEET AND
INDEX OF DRAWINGS

These documents are copyrighted by Aldrich + Elliott (A+E), with all rights reserved. No duplication or distribution by anyone other than Blueprints Etc., or those authorized in writing by A+E to print and distribute these documents, is allowed by law. Violation of this copyright is a finable offense in Vermont and violators will be prosecuted. Copy shops and view rooms are specifically prohibited from making copies of these copyrighted documents for distribution and sale. View rooms may scan these documents for viewing only and bidders may purchase a CD that contains the documents in pdf format. However the stamped paper reproducible version of the documents will govern and prevail in the event of any discrepancy.

DESIGNED RRW	PROJECT NO. 23054
DRAWN EDS	T
CHECKED JRL	
DATE FEB. 2024	

PLAN-EXISTING

Legend for existing plan symbols including Waterline, Sanitary Sewer, Culvert-Drain, Overhead Power, Underground Electrical Conduit, Underground Telephone Conduit, Property Line, Right-of-Way, Major/Minor Contour, Fence-Miscellaneous, Tree-Hedge Line, Swale, Bituminous Pavement, Gravel Road or Drive, Garden, Stone Wall, Cap, Reducer, Gate Valve, Curb Stop, Hydrant, Well, Manhole, Clean Out, Catch Basin, Utility Pole, Light Pole, GUY Wire, Deciduous Tree, Coniferous Tree, Bollard, Survey Station, Property Marker, Miscellaneous Sign, Soil Boring/Probe, Electrical Pedestal, Electrical Pull Box, Telephone Pedestal, Shrub, Flag Pole, Mailbox, Wetland, Wetland Boundary, Wetland Buffer Zone.

PROFILE-EXISTING

Legend for existing profile symbols including Ground Surface, Pipe, Utility Crossing, Soil Boring/Probe (SB-1, SB-1, LP-1, PL-1), and notes for NLTD (NO LEDGE TO DEPTH) and REF (REFUSAL).

PLAN-PROPOSED

Legend for proposed plan symbols including Sanitary Sewer, Permanent Easement, Temporary Easement, Major/Minor Contour, Tree-Clearing Limits, Swale, Cap, Manhole, and Test Pit.

PROFILE-PROPOSED

Legend for proposed profile symbols including Ground Surface, Pipe, Insulation, Bend-Tee, and Wye (8" x 4" WYE).

GENERAL CONSTRUCTION NOTES

- 1. SAFETY
A. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE SAFETY OF EMPLOYEES ON THE PROJECT...
B. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE V.O.S.H.A. SAFETY REQUIREMENTS...
C. THE CONTRACTOR SHALL PROVIDE ADEQUATE EQUIPMENT AND FACILITIES AS ARE NECESSARY...
D. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY TRAFFIC CONTROL SIGNS...
E. THE CONTRACTOR SHALL MAINTAIN ALTERNATING ONE-WAY TRAFFIC ON ALL STREETS, ROADS, AND HIGHWAYS...

2. EASEMENTS
A. THE CONTRACTOR SHALL PERFORM ALL WORK WITHIN TEMPORARY CONSTRUCTION EASEMENT LIMITS...
B. WHERE NO TEMPORARY CONSTRUCTION EASEMENT IS SHOWN ON CONTRACT DRAWINGS...

3. PROTECTION OF WORK
A. THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR THE PROTECTION OF ALL BUILDINGS, STRUCTURES AND UTILITIES...
B. THE CONTRACTOR SHALL CAREFULLY SUPPORT AND PROTECT ANY UTILITIES, STRUCTURES, PIPE LINES, AND CONDUITS...

4. MAINTENANCE OF FLOWS
A. THE CONTRACTOR SHALL AT THE CONTRACTOR'S OWN COST, MAKE PROVISIONS FOR MAINTAINING FLOW THROUGH EXISTING FORCE MAINS, SEWER LINES, WATERLINES...

5. BURIED UTILITIES
A. UNDERGROUND UTILITIES LOCATIONS ARE APPROXIMATE ONLY...
B. THE CONTRACTOR SHALL EXCAVATE TEST PITS AS SHOWN ON THE DRAWINGS OR AS APPROVED BY THE ENGINEER...
C. EXISTING UTILITIES SHALL BE PROTECTED OR REMOVAL AND REPLACEMENT SHALL BE COORDINATED WITH THE APPROPRIATE COMPANY...
D. THE CONTRACTOR SHALL PERMANENTLY PLUG ALL EXISTING LINES WHICH ARE REPLACED BY NEW ONES...

6. CONSTRUCTION
A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HOLDING UTILITY POLES AS NECESSARY...
B. THE CONTRACTOR SHALL INSTALL A MECHANICAL PLUG IN THE END OF ALL PIPE WORK AT THE COMPLETION OF EACH WORK DAY...

6. CONSTRUCTION (CONT.)
D. THE CONTRACTOR SHALL RESTORE DRIVEWAYS, LAWNS, AND SIDEWALKS IMMEDIATELY AFTER WORK IS COMPLETE.

AE Aldrich + Elliott WATER RESOURCE ENGINEERS
6 Market Place, Suite 2
Essex Jct., VT 05452
P: 802.879.7733
AEEngineers.com





Table with columns: CHECKED, DESCRIPTION, DATE, NO.

TOWN OF CASTLETON, VERMONT

CRYSTAL HEIGHTS SEWERLINE EXTENSION CONTRACT No.1

GENERAL CONSTRUCTION NOTES AND LEGEND

Table with columns: DESIGNED (RRW), DRAWN (EDS), CHECKED (JRL), DATE (FEB. 2024), PROJECT NO. (23054), and a large number 1.



PROFILE
SCALE: HORIZ.=1"=30'
VERT.=1"=3'

CHECKED	DESCRIPTION	DATE	No.


TOWN OF
CASTLETON,
VERMONT

CRYSTAL HEIGHTS
SEWERLINE
EXTENSION
CONTRACT No.1

PROPOSED PLAN
AND PROFILE
STA. 8+00 TO 16+26


DESIGNED RRW	PROJECT NO. 23054
DRAWN EDS	3
CHECKED JRL	
DATE FEB. 2024	

C:\Users\khuu\Documents\AE\Projects\23054-CASTLETON CRYSTAL HEIGHTS\23054.dwg, 1/24/2024 7:54:04 PM




- NOTES:**
- NO MECHANICAL TAMPERS SHALL BE USED DIRECTLY OVER PVC PIPE TO ENSURE PIPE IS NOT DAMAGED.
 - BEDDING TO PROVIDE A FIRM, STABLE, CONTINUOUS AND UNIFORM SUPPORT FOR THE FULL LENGTH OF PIPE.
 - FOR INITIAL BACKFILL CONTRACTOR CAN USE 3/4" CRUSHED STONE OR SAND BORROW.

A
4 TYPICAL SEWER PIPE TRENCH DETAIL
SCALE: NONE




- MANHOLE NOTES:**
- INVERTS OF MANHOLE SHALL BE LINED WITH PRECAST CONCRETE.
 - PROVIDE SMOOTH SWEEPING TRANSITIONS BETWEEN INVERTS OF INLET AND OUTLET PIPES. NO GAP IS ALLOWED BETWEEN THE SHELF/TROUGH AND INNER WALL OF MANHOLE AROUND THE PIPE.
 - IF DEPTH OF MANHOLE IS 7 FEET OR LESS FROM RIM TO CENTERLINE INVERT THEN A FLAT TOP SHALL BE INSTALLED IF DEPTH OF MANHOLE FROM RIM TO CENTERLINE INVERT IS MORE THAN 7 FEET THEN A CONICAL TOP SHALL BE INSTALLED.

B
4 TYPICAL SANITARY SEWER CONICAL MANHOLE DETAIL
SCALE: NONE




- MANHOLE NOTES:**
- INVERTS OF MANHOLE SHALL BE LINED WITH PRECAST CONCRETE.
 - PROVIDE SMOOTH SWEEPING TRANSITIONS BETWEEN INVERTS OF INLET AND OUTLET PIPES. NO GAP IS ALLOWED BETWEEN THE SHELF/TROUGH AND INNER WALL OF MANHOLE AROUND THE PIPE.
 - IF DEPTH OF MANHOLE IS 7 FEET OR LESS FROM RIM TO CENTERLINE INVERT THEN A FLAT TOP SHALL BE INSTALLED IF DEPTH OF MANHOLE FROM RIM TO CENTERLINE INVERT IS MORE THAN 7 FEET THEN A CONICAL TOP SHALL BE INSTALLED.

C
4 TYPICAL SANITARY SEWER FLAT TOP MANHOLE DETAIL
SCALE: NONE




- NOTES:**
- NEW SEWER MANHOLES OVER EXISTING SEWERLINES SHALL BE "DOG HOUSE" TYPE MANHOLES WITH CAST-IN-PLACE BASES. DO NOT SET ANY RISER SECTIONS UNTIL CAST-IN-PLACE BASE AND BOTTOM RISER HAS SET FOR MIN. 24 HOURS.
 - THE BOTTOM RISER SHALL BE A 5'x4' HIGH RISER WITH (2) 18" KNOCK OUTS AT BOTTOM OF RISER FOR THE EXISTING 12" VC PIPE.
 - THE AREA AROUND THE 12" PIPES SHALL BE SEALED WATER TIGHT. APPLY (2) COATS OF ASPHALTIC SEALANT TO CAST-IN-PLACE BASE AND SEALED AREAS AROUND 12" PIPES.
 - INVERTS OF MANHOLE SHALL BE LINED WITH HARD SEWER BRICK.
 - PROVIDE SMOOTH SWEEPING TRANSITIONS BETWEEN INVERTS OF INTERSECTING PIPES.

D
4 TYPICAL DOG HOUSE MANHOLE DETAIL
SCALE: NONE



E
4 SANITARY MANHOLE PLAN
SCALE: NONE



- NOTES:**
- ALIGN WYE SO AS THE SERVICE END IS DIRECTED UPSTREAM TO THE SEWAGE FLOW.
 - THREE (3) TIES SHALL BE TAKEN OF THE CAPPED END OF ALL LATERALS.
 - EACH NEW SERVICE LATERAL TO BE PRESSURE TESTED ALONG WITH SEWER.
 - EXTEND EACH SERVICE LATERAL TO THE LIMITS SHOWN ON THE DRAWINGS AND RECONNECT TO EXISTING SERVICE LATERALS AFTER TESTING.
 - MAINTAIN A CONSTANT SLOPE FROM WYE TO END CAP. MINIMUM SLOPE SHALL BE 1/4"/FT FOR 4" SERVICES AND 0.006 FT/FT FOR 6" SERVICES.
 - PROVIDE INSULATION AS FOLLOWS:
 - FOR PLOWED AREAS WHERE 5' OF COVER CANNOT BE MAINTAINED.
 - FOR UNPLOWED AREAS WHERE 4' OF COVER CANNOT BE MAINTAINED.

F
4 TYPICAL SANITARY SEWER SERVICE DETAIL
SCALE: NONE


CHECKED	DESCRIPTION	DATE	NO.

TOWN OF CASTLETON, VERMONT

CRYSTAL HEIGHTS SEWERLINE EXTENSION CONTRACT No.1

SEWER DETAILS I


DESIGNED RRW	PROJECT NO. 23054
DRAWN EDS	4
CHECKED JRL	
DATE FEB. 2024	



NOTES:

- 1. STAGGER INSULATION JOINTS SO THAT NO JOINTS OF THE TWO (2) LAYERS ARE ONE OVER THE OTHER.
- 2. TO BE INSULATED AS DIRECTED BY THE ENGINEER.
- 3. INSULATION TO BE UTILIZED AT ALL LOCATIONS INDICATED ON PLAN SHEETS AND OTHER AREAS WHERE 6\"/>

A
5 TYPICAL PIPE INSULATION DETAIL
 SCALE: NONE






NOTES:


- 1. THRUST BLOCKS SHALL BE PROVIDED AT ALL PRESSURIZE PIPELINE TEES, 90° AND 45° BENDS, REDUCERS, END CAPS, AND HYDRANTS.
- 2. ALL THRUST BLOCKS SHALL BE CLASS "B" CONCRETE. SEE SPEC SECTION 03305
- 3. CONCRETE SHALL BE PLACED SO AS NOT TO HAMPER THE FUTURE REMOVAL OF A FITTING.
- 4. ALL FITTINGS ARE TO BE WRAPPED WITH POLYETHYLENE.
- 5. MINIMUM BEARING SURFACE IS BASED ON A SOIL TYPE WITH AASHTO CLASSIFICATION OF GROUP A-3 AND A-4 FOR GRANULAR AND SANDY/SILTY MATERIALS. OTHER SOIL TYPES MAY REQUIRE AN INCREASE IN THE BEARING SURFACE, AS IDENTIFIED DURING CONSTRUCTION.

MINIMUM BEARING SURFACES					
SQUARE FEET					
PIPE DIA.	TEE	HYD.	90° BEND'	45° BEND	END CAP
12"	14	—	17	10	14
8"	8	—	14	7	8
6"	5	6	6	4	5

C
5 TYPICAL THRUST BLOCK DETAILS
 SCALE: NONE



TYPICAL SECTION
 SCALE: NONE



NOTES:

- 1. TRACER WIRE SHALL BE TERMINATED AT EACH END IN A FLUSH MOUNT ACCESS BOX. ACCESS BOX SHALL HAVE A CAST IRON LID THAT CAN BE LOCKED AND OPENED WITH A STANDARD PENTAGON HEAD KEY WRENCH. TRACER WIRES SHALL BE STRIPPED AND ATTACHED TO STAINLESS STEEL SCREWS MOUNTED TO THE UNDERSIDE OF THE LID. SUFFICIENT SLACK (12" MIN.) SHALL BE LEFT IN WIRE LENGTH SO COVER CAN BE LIFTED WITH WIRE INTACT. TRACER WIRE ACCESS BOX SHALL BE LOCATED OVER PIPE LINE TO WHICH TRACER LEAD IS ATTACHED AND SET TO GRADE. TRACER WIRE ACCESS BOX SHALL BE VALVCO TWAB OR APPROVED EQUAL.
- 2. TRACER WIRE ACCESS POINTS SHALL IN GENERAL BE NO MORE THAN 500 FEET APART.

C
5 TRACER WIRE ACCESS BOX DETAIL
 SCALE: NONE


CHECKED	DESCRIPTION	DATE	No.

TOWN OF CASTLETON, VERMONT

CRYSTAL HEIGHTS SEWERLINE EXTENSION CONTRACT No.1

SEWER DETAILS II

DESIGNED RRR	PROJECT NO. 23054
DRAWN EDS	5
CHECKED JRL	
DATE FEB. 2024	



NOTES:

1. THE TRENCH PAYMENT LIMIT SHALL BE AS FOLLOWS:


DEPTH OF PIPE	TRENCH LIMIT
0 TO 10 FEET	O.D.+5'
GREATER THAN 10 FEET	O.D.+7'

2. THE TRENCH PAYMENT LIMIT APPLIES TO ALL TRENCHES AND ALL SURFACES. SURFACE REPLACEMENT AND RESTORATION OUTSIDE OF THE TRENCH PAYMENT LIMITS WILL BE AT THE CONTRACTOR'S EXPENSE.

3. WHERE CONCRETE ROADWAY IS REMOVED PERPENDICULAR TO THE ROADWAY (OR FLOW OF TRAFFIC), THE EDGES OF THE SECTION, TO BE REMOVED WITHIN THE TRENCH PAYMENT LIMITS, SHALL BE SAWCUT STRAIGHT PRIOR TO REMOVAL OF THE CONCRETE.

4. WHERE THE CONTRACTOR ENCOUNTERS CONCRETE ROADWAY DURING TRENCH EXCAVATION, THE BITUMINOUS PAVEMENT SHALL BE CUT BACK AT A MINIMUM OF 6" OVER THE CONCRETE ROADWAY.

A
6 **TRENCH PAYMENT LIMITS**
SCALE: NONE




CONTRACTOR NOTE:
KEEP TRENCH TOP AS NARROW AS PRACTICAL (SEE TRENCH PAYMENT LIMITS)

NOTES:


- IT IS INTENDED THAT THE CONTRACTOR AVOID ANY DAMAGE TO EXISTING ROADWAY OR SHOULDER PAVEMENT. HOWEVER WHERE PIPE MUST BE INSTALLED WITHIN PAVED SURFACE, BITUMINOUS PAVEMENT REPAIR SHALL BE PAID IN ACCORDANCE WITH "TRENCH PAYMENT LIMITS" AND UNIT PRICE BID. PAVEMENT REPAIR OUTSIDE APPROVED LIMITS SHALL BE AT CONTRACTOR'S EXPENSE.
- ALL PAVEMENT AND GRAVEL SUBBASE SHALL HAVE A MINIMUM COMPACTED THICKNESS AS SHOWN IN "SCHEDULE OF TRENCH REPAIR THICKNESSES" SEE DETAIL D/13.
- SEE SPECIFICATIONS FOR FURTHER INFORMATION.
- ALL EXISTING PAVEMENT MARKINGS SHALL BE RE-PAINTED AS NECESSARY.
- IF NECESSARY, SHOULDER SHALL BE REPLACED TO A CONDITION EQUAL TO OR BETTER THAN BEFORE CONSTRUCTION ACTIVITIES.

B
6 **EDGE OF PAVEMENT TRENCH REPAIR DETAIL**
SCALE: NONE



CONTRACTOR NOTE:
KEEP TRENCH TOP AS NARROW AS PRACTICAL (SEE TRENCH PAYMENT LIMITS)

C
6 **TYPICAL GRAVEL ROAD/DRIVE/ OR SHOULDER REPAIR DETAIL**
SCALE: NONE



CONTRACTOR NOTE:
KEEP TRENCH TOP AS NARROW AS PRACTICAL. SEE TRENCH PAVEMENT PAYMENT LIMITS

PAVEMENT REPAIR NOTES:

- ALL PAVEMENT SHALL HAVE A MINIMUM COMPACTED THICKNESS AS SHOWN.
- IF NECESSARY, SHOULDER SHALL BE REPLACED TO A CONDITION EQUAL OR BETTER THAN BEFORE CONSTRUCTION ACTIVITIES.
- ALL EXISTING PAVEMENT MARKINGS SHALL BE RE-PAINTED AS NECESSARY.
- IT IS INTENDED THAT CONTRACTOR AVOID ANY DAMAGE TO EXISTING ROADWAY OR SHOULDER PAVEMENT. HOWEVER WHERE PIPE MUST BE INSTALLED WITHIN 3'-0" OF PAVED SURFACE, BITUMINOUS PAVEMENT REPAIR SHALL BE PAID IN ACCORDANCE WITH "TRENCH PAYMENT LIMITS" AND UNIT PRICE BID. PAVEMENT REPAIR OUTSIDE APPROVED LIMITS SHALL BE AT CONTRACTOR'S EXPENSE.

SCHEDULE OF TRENCH REPAIR THICKNESSES

	STREETS	DRIVEWAYS
BITUMINOUS PAVEMENT		
TOP COURSE - TYPE III	1-1/2"	1"
BASE COURSE - TYPE II	3"	1"
FINE GRADED GRAVEL SUBBASE, VAOT ITEM 704.05A	12"	12"
DENSE GRADED GRAVEL SUBBASE, VAOT ITEM 704.06A	12"	---

D
6 **TRENCH PAVEMENT REPAIR DETAIL**
SCALE: NONE

AE
Aldrich + Elliott
WATER RESOURCE ENGINEERS
6 Market Place, Suite 2
Essex Jct., VT 05452
P: 802.879.7733
AEngineers.com

CHECKED	DESCRIPTION	DATE	No.


TOWN OF
CASTLETON,
VERMONT

CRYSTAL HEIGHTS
SEWERLINE
EXTENSION
CONTRACT No.1

ROADWAY DEATAILS

DESIGNED RRW	PROJECT NO. 23054
DRAWN EDS	6
CHECKED JRL	
DATE FEB. 2024	


C:\Users\shansilwan\Aldrich + Elliott - PC\Aldrich + Elliott - Shared - Documents\CAD\vacproj\projects_2\23054-CASTLETON_CRYSTAL HEIGHTS\23054-6.dwg, 1/24/2024 12:52:59 PM



NOTES:


1. SILT FENCE SHALL BE PRE-FABRICATED EROSION CONTROL FENCE BY MIRAFI OR APPROVED EQUAL.
2. INSTALL WHERE SHOWN ON PLANS. THE FENCE SHALL BE INSTALLED PARALLEL TO CONTOURS WHERE POSSIBLE. THE ENDS OF THE FENCE SHOULD BE CURVED UPHILL TO PREVENT FLOW AROUND THE ENDS.
3. SECTIONS OF THE SILT FENCE SHALL BE JOINED TO OVERLAP BY FOLDING FABRIC AROUND EACH POST ONE FULL TURN. DRIVE POSTS TIGHTLY TOGETHER AND SECURE TOPS OF POSTS BY TYING OFF WITH CORD OR WIRE TO PREVENT FLOW-THROUGH OR BUILT-UP SEDIMENT AT JOINT.
4. INSPECT ALL SILT FENCE AT LEAST ONCE A WEEK AND WITHIN 24 HOURS AFTER EACH RAINFALL. MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND SEDIMENT REMOVED WHEN SEDIMENT REACHES 1/3 HEIGHT OF THE SILT FENCE.
5. UPON FINAL STABILIZATION OF THE AREA UPHILL OF THE FABRIC, THE FABRIC SHALL BE REMOVED WITH THE APPROVAL OF THE OWNER.

A
7 **TYPICAL TEMPORARY SILT FENCE DETAIL**
 SCALE: NONE



EROSION CONTROL NOTES:

1. EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED PRIOR TO PERFORMING ANY EARTHWORK DOWNSTREAM OF THE DISTURBED AREA AND AS DIRECTED BY THE OWNER. THE MEASURES SHALL BE MAINTAINED UNTIL THE UPSTREAM DISTURBED AREA HAS BEEN PERMANENTLY STABILIZED AND AS DIRECTED BY THE OWNER. THE CONTRACTOR SHALL INSTALL ALL TEMPORARY EROSION PREVENTION AND SEDIMENT CONTROL MEASURES AS SHOWN ON THE CONTRACT DRAWINGS. THE CONTRACTOR SHALL PROVIDE ANY ADDITIONAL MEASURES DETERMINED NECESSARY IN THE FIELD.
2. SILT FENCE SHALL BE INSTALLED, AS SHOWN ON THE CONTRACT DRAWINGS PRIOR TO ANY EARTHWORK DOWNSTREAM OF THE DISTURBED AREA AND AS DIRECTED BY THE OWNER. THE SILT FENCE SHALL BE MAINTAINED AND CLEANED UNTIL THE UPSTREAM DISTURBED AREA HAS BEEN PERMANENTLY STABILIZED AND AS DIRECTED BY THE OWNER. WHERE POSSIBLE NATURAL DRAINAGE WAYS SHALL BE UTILIZED AND LEFT OPEN TO REMOVE EXCESS SURFACE WATER.
3. DEGRADABLE EROSION CONTROL BLANKETS SHALL BE INSTALLED ON DISTURBED VEGETATED SLOPES THAT HAVE SLOPES GREATER THAN 3:1. THE CONTRACTOR SHALL INSTALL THE DEGRADABLE EROSION CONTROL BLANKETS PER MANUFACTURER'S RECOMMENDATIONS.
4. PROPER EROSION CONTROLS SHALL BE PROVIDED AROUND STOCKPILED EXCAVATED MATERIALS. THESE CONTROLS MAY INCLUDE, BUT NOT BE LIMITED TO, THE FOLLOWING METHODS OF EROSION PREVENTION AND SEDIMENT CONTROL: PERIMETER SILT FENCE; INTERCEPTOR DRAINAGE DITCHES; VELOCITY REDUCTION DAMS IN DRAINAGE DITCHES; TEMPORARY BANK PROTECTION SUCH AS RIPRAP, MATTING, OR ARTIFICIAL COVERING; STONE CHECK DAM CONTROL SYSTEMS; SPECIAL STOCKPILING METHODS; AND WATER BARS.
5. THE CONTRACTOR SHALL PROVIDE A MECHANICAL SWEEPER AND SHALL SWEEP CLEAN THE ROADS IN THE CONSTRUCTION AREAS AS REQUIRED TO REMOVE ACCUMULATED SEDIMENT AND PREVENT SEDIMENT RUNOFF INTO RECEIVING WATERS AND AS DIRECTED BY THE OWNER.
6. TEMPORARY EROSION CONTROL MEASURES SHALL BE UTILIZED BY THE CONTRACTOR AS REQUIRED TO PREVENT ANY SEDIMENTATION FROM RUNNING INTO RECEIVING WATERS. THE CONTRACTOR SHALL MAKE EVERY EFFORT TO MINIMIZE ANY IMPACT OF THE ON-SITE SURFACE RUNOFF ON THE QUALITY OF THE RECEIVING WATERS.
7. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE DISTURBED AT ANY ONE TIME DURING CONSTRUCTION. WHEN LAND IS DISTURBED DURING CONSTRUCTION, THE DISTURBANCE SHALL BE KEPT TO THE SHORTEST PRACTICAL DURATION AS APPROVED BY THE OWNER. LAND SHALL NOT BE LEFT DISTURBED DURING THE WINTER MONTHS AND OVERWINTER STABILIZATION MEASURES SHALL BE INSTALLED PRIOR TO OCTOBER 15TH.
8. ALL DISTURBED AREAS AND SIDE SLOPES WHICH ARE FINISH GRADED WITH NO FURTHER CONSTRUCTION TO TAKE PLACE SHALL BE LOAMED, LIMED, FERTILIZED, SEEDED, AND MULCHED WITHIN 48 HOURS OF FINAL GRADING. A MINIMUM OF 3 INCHES OF LOAM SHALL BE PLACED.
9. NO DISTURBED AREAS SHALL BE LEFT UNSEEDED AND UNMULCHED FOR MORE THAN SEVEN (7) DAYS. DISTURBED AREAS WHICH WILL BE REGRADED LATER DURING CONSTRUCTION SHALL BE MULCHED AND SEEDED WITH RYE GRASS TO PREVENT EROSION. STRAW MULCH SHALL BE APPLIED TO ALL FRESHLY SEEDED AREAS AT THE RATE OF 2 TONS PER ACRE. BALES SHALL BE UNSPOILED, AIR DRIED, AND FREE FROM WEED, SEEDS, AND ANY COARSE MATERIAL. CONTRACTOR MAY ALSO USE EROSION MATTING OR OTHER APPROVED METHODS OF TEMPORARY COVER.
10. IF SUBSURFACE CONTAMINATED SOILS ARE ENCOUNTERED, WORK WILL STOP AND THE PROJECT OWNER SHALL BE NOTIFIED UPON DISCOVERY OF THE CONDITION. OWNER SHALL CONTACT SPILLS/SITES MANAGEMENT SECTION OF THE VERMONT DEC. SOIL STOCKPILING AND DISPOSAL OPTIONS MAY BE AFFECTED BY THE CHARACTERISTICS OF THE AFFECTED MATERIAL.
11. ALL EROSION PREVENTION AND SEDIMENT CONTROL STRUCTURES AND MEASURES SHALL BE INSPECTED BY OR UNDER THE DIRECTION OF THE ON-SITE COORDINATOR AT LEAST EVERY SEVEN (7) CALENDAR DAYS AND AS SOON AS POSSIBLE BUT NO LATER THAN 24 HOURS AFTER ANY STORM EVENT WHICH GENERATES A DISCHARGE OF STORMWATER RUNOFF FROM THE CONSTRUCTION SITE.
12. AFTER ALL UPSTREAM DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED AND AS DIRECTED BY THE OWNER, THE DOWNSTREAM TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED AND THE ACCUMULATED SEDIMENT PROPERLY DISPOSED OF. THE AREA DISTURBED BY THE REMOVAL OF TEMPORARY MEASURES SHALL BE PREPARED, SEEDED, AND MULCHED.



NOTES:

1. UNDERGRATE FABRIC INLET PROTECTION SHALL ONLY BE USED WHERE SHOWN ON PLANS. IT SHOULD ONLY BE USED FOR EXISTING CATCH BASINS IN EXISTING PAVED AREAS FOR LINEAR PIPELINE PROJECTS WHERE AMOUNT OF SEDIMENT RUN OFF IS MINIMAL AND DURATION OF CONSTRUCTION IS SHORT.
2. LIFT THE GRATE AND INSTALL FILTER FABRIC (MIRAFI 140NL OR EQUAL) OVER THE FRAME, AND THEN SET GRATE BACK IN PLACE.
3. INSPECT EACH INLET AT LEAST ONCE A WEEK AND WITHIN 24 HOURS AFTER EVERY RAINFALL. REPAIR AND REPLACEMENT OF INLET PROTECTION SHALL BE MADE AT TIME OF INSPECTION.
4. UPON STABILIZATION OF THE AREA UPSTREAM FROM THE INLET, THE PROTECTION FABRIC SHALL BE REMOVED WITH THE APPROVAL OF THE OWNER.

B
7 **TYPICAL TEMPORARY INLET PROTECTION DETAIL**
 SCALE: NONE

CHECKED	DESCRIPTION	DATE	NO.

TOWN OF
 CASTLETON,
 VERMONT

CRYSTAL HEIGHTS
 SEWERLINE
 EXTENSION
 CONTRACT No.1

**EROSION CONTROL
 DETAILS AND NOTES**

DESIGNED RRW	PROJECT NO. 23054
DRAWN EDS	7
CHECKED JRL	
DATE FEB. 2024	